

Computer-Aided Project Management

*A Visual Scheduling
and Management System*

Computer-Aided Project Management

A Visual Scheduling and Management System

Spiro N. Pollalis

Harvard University

Vieweg Verlag
Wiesbaden, Germany

This work presents a new efficient and effective method for the control and allocation of resources employed in the creation of a product. While most of the examples in the text refer to manufacturing of buildings, the method is general, applicable to the generation of even non-physical products such as research projects.

The superiority of the Pollalis system over traditional analytical Operations Research and Program Scheduling, in offering an easier comprehensive view of the process and in coping flexibly with qualitative data, results from the choice of representation for the specific problem of reasoning about actions. Visual descriptions of the system require less prerequisites to be comprehended and "cost" less effort to be used.

Prof. Alexander Tzonis
TU-Delft

to Tatiana

Contents

Contents	ix
List of Figures.....	xiii
List of Tables	xviii
Acknowledgments	xix

PREFACE	1
---------------	---

INTRODUCTION.....	5
1.1 Project Management	5
1.2 Scheduling	6
1.3 Design Considerations	8
1.4 Organization of Chapters	9

PART I***THE VISUAL SCHEDULING AND MANAGEMENT SYSTEM***

QUANTIFIED BARS.....	13
2.1 The Quantified Bar	14
2.2 Alternative Displays.....	18
2.3 Monitoring a Task.....	22
2.4 Updating a Task	23
2.5 Variables of the Quantified Bar	26

QUANTIFIED BAR CHARTS	29
3.1 The Quantified Bar Chart	30
3.2 Independent and Dependent Tasks	32
3.3 Quantified Bars on the Chart.....	35
3.4 Operations on Quantified Bar Charts	40
3.5 Constraints on the Quantified Bars	51
3.6 Display of Capacity	52
3.6.1 Scheduling of Classes	52

iv Table of Contents

3.6.2	Visualization of Transportation Capacity	55
TEMPLATES		59
4.1	The Template	61
4.2	Input and Output	62
4.3	Visual Leveling of Resources.....	65
4.4	Monitoring and Forecasting.....	69
THE MATRIX-BALANCED CHART.....		75
5.1	Repeating Tasks	76
5.2	The Matrix-Balanced Chart	78
5.3	Line of the Diagonals	79
5.4	Balancing the Matrix Chart.....	82
5.5	Constituent Matrix Chart	91
5.6	Monitoring Different Locations	92
5.7	Scheduling Assembly Lines	94
HIERARCHICAL REPRESENTATION.....		101
6.1	Folding-up	102
6.2	Description of the Hierarchical System	104
6.2.1	Microtemplate Schedules.....	107
6.2.2	Template Schedules	108
6.2.3	Matrix-Balanced Schedules	110
6.2.4	Master Schedule.....	118
6.2.5	Link with Other Systems	118
6.3	Changes in the Schedules	118
6.3.1	Upward Changes.....	119
6.3.2	Downward Changes.....	119
6.4	Monitoring and Updating	120

PART II
THE VISUAL SCHEDULING AND MANAGEMENT SYSTEM
AND THE STATE-OF-PRACTICE REPRESENTATIONS

STATE-OF-PRACTICE REPRESENTATIONS.....	125
7.1 Breakdown of Projects	126
7.2 Milestone Chart	127
7.3 Gantt Chart (bar Chart	128
7.4 Network Diagrams.....	130
7.4.1 Task Precedences on a Network.....	131
7.4.2 Tasks on the Nodes Networks	131
7.4.3 Tasks on the Arrows Networks.....	132
7.4.4 The Critical Path Method	134
7.4.5 The Gantt Chart as Complementary Representation	136
7.5 Line of Balance Chart.....	137
7.6 Graphics in Project Scheduling Software.....	140
COMPARISON OF THE VSMS TO THE STATE-OF-PRACTICE REPRESENTATIONS.....	141
8.1 Comparison for Scheduling.....	142
8.1.1 Visual Display of Work.....	142
8.1.2 Visual Display of Resources.....	144
8.1.3 Visual Scheduling of Repeating Tasks.....	148
8.1.4 Hierarchical Structure.....	149
8.1.5 Visual Identification of the Critical Path.....	149
8.1.6 Feasibility Studies.....	151
8.2 Comparison for Management.....	152
8.2.1 Control of the Project	152
8.2.2 Updating the Project	154
8.2.3 Visual Recognition of Errors	156
8.2.4 Communication	156

PART II
THE VISUAL SCHEDULING AND MANAGEMENT SYSTEM
AND THE STATE-OF-PRACTICE REPRESENTATIONS

SCHEDULING THE CONSTRUCTION OF A HOTEL	161
9.1 The Project.....	163
9.2 The Construction of the Structural Frame	164
9.2.1 Quantities of Work and Productivity.....	164
9.2.2 Assignment of Workers	166
9.3 Scheduling the Construction of the Frame.....	175
9.3.1 The Microtemplate Schedule.....	175
9.3.2 The Template for Structural Work	178
9.3.3 The Matrix-Balanced Chart	178
9.4 Scheduling the Finishing of the Building	180
9.4.1 Finishing the Bathrooms.....	181
9.4.2 Finishing the Guest Rooms.....	184
9.4.3 The Combined Matrix-Balanced Chart for Bathrooms and Guest Rooms	184
9.4.4 Recovering a Delay in Finishing	189
THE RENOVATION OF A BUILDING INTERIOR.....	193
10.1 The Project.....	194
10.2 Scheduling the 26th Floor	198
10.2.1 Quantities of Work and Productivity.....	198
10.2.2 Duration and Precedences of Tasks.....	199
10.2.3 Adjustments for Resource Leveling	203
10.3 Executing the Renovation of the 26th Floor	208
10.3.1 Control Template In-Progress.....	209
10.3.2 Final Control Template.....	216
10.4 Planning the Rest of the Project.....	218
10.4.1 Combined Templates	222
10.4.2 Matrix-Balanced Chart	223
10.5 VSMS in the Construction Process	225
10.5.1 VSMS as an Analytical Tool.....	225
10.5.2 VSMS as a Communication Device	226

10.5.3 VSMS as a Recording Device 227

BIBLIOGRAPHY 229

CREDITS 237

INDEX 239

List of Figures

Fig. 2.1. The quantified bar, displayed in two dimensions..... 14

Fig. 2.2. Alternative scheduling of a task with quantified bars. 15

Fig. 2.3. Relationship between duration and intensity. 15

Fig. 2.4. The connoting bar. 16

Fig. 2.5. Planning the brick laying task, either for 4 or for 6 days. 17

Fig. 2.6. Scheduling a task with a variable intensity. 17

Fig. 2.7. Relationships between work, a resource and the corresponding cost, as related to the duration of the task. 19

Fig. 2.8. Relationships between work, personpower and wages. 20

Fig. 2.9. Planning a task, shown in alternative displays of the quantified bar with quantities work, person-time, wages and cost of materials. 21

Fig. 2.10. Monitoring the task of Fig. 2.9 at the completion of the 5th day with quantities work, person-time, wages and cost of materials..... 22

Fig. 2.11. Updating the planning of the task of Fig. 2.9 with areas representing work, personpower, wages and materials..... 25

Fig. 3.1. The quantified bar chart. 30

Fig. 3.2. The connoting bar chart. 31

Fig. 3.3. Independent tasks. 32

Fig. 3.4. Parallel tasks..... 32

Fig. 3.5. Continuous or serial tasks. 33

Fig. 3.6. Overlapping or forced overlapping tasks. 33

Fig. 3.7. Common start tasks. 34

Fig. 3.8. Common finish tasks..... 34

Fig. 3.9. Related quantified bars..... 36

Fig. 3.10. Quantified bar chart for the construction of a typical floor, intensity personpower. 37

Fig. 3.11. Horizontal shift of a task. 40

Fig. 3.12. Expansion or contraction of a task. 41

Fig. 3.13. Addition of continuous tasks and partition to continuous tasks..... 41

Fig. 3.14. Addition of parallel tasks and partition to parallel tasks..... 42

Fig. 3.15. Vertical shift of a task. 42

Fig. 3.16.	Quantified bars for the construction of a typical room	44
Fig. 3.17.	Studies of float times for the construction of a typical room, intensity personpower.	46
Fig. 3.18.	Quantified bar chart for the construction of a typical floor, intensity personpower.	47
Fig. 3.19.	Quantified bar chart for the construction of a typical floor, intensity personpower. Studies to introduce two crews at a time.	48
Fig. 3.20.	Quantified bar chart for the construction of a typical floor with two crews at a time, intensity personpower.	49
Fig. 3.21.	Final quantified bar chart for the construction of a typical floor, second crew always M&E, intensity personpower.	50
Fig. 3.22.	Scheduling of classes, intensities capacities of classrooms and all students.....	53
Fig. 3.23.	Visual display of the range of the aircrafts and the corresponding payload, for maximum range and for maximum payload.	55
Fig. 3.24.	Visual display of the cruising time of the aircrafts and the corresponding payload, for maximum range and for maximum payload.	56
Fig. 3.25.	Visual display of the seating capacity of the aircrafts and the actual number of passengers in a specific flight.	56
Fig. 4.1.	Template for the planning of the construction of a typical floor.	60
Fig. 4.2.	Quantified bars without established precedences.	64
Fig. 4.3.	The development of a software product.....	67
Fig. 4.4.	Preparations for an art gallery exhibition.....	68
Fig. 4.5.	Construction site daily report for the control of the company's workers.	70
Fig. 4.6.	Construction site daily report for the control of the subcontractors.	71
Fig. 4.7.	Control template of planning and monitoring the construction of a typical floor.	72
Fig. 5.1.	The concept of the matrix-balanced chart, indicating its dimensions.....	77
Fig. 5.2.	The line of the diagonals for tasks with the same quantity in all locations.	79

x List of Figures

Fig. 5.3. The line of the diagonals indicating a learning curve from location to location.....81

Fig. 5.4. Productivity and the quantified bar displaying personpower.....81

Fig. 5.5. The scheduling of all floors as it would be optimal for a typical floor, intensity personpower.....84

Fig. 5.6. The matrix-balanced chart, intensity personpower.85

Fig. 5.7. Progression of repeating tasks from location to location, intensity personpower.86

Fig. 5.8. Studies of float time among the tasks87

Fig. 5.9. Translation of the tasks along the vertical axis in order to develop the constituent matrix chart, intensity personpower.....90

Fig. 5.10. Auxiliary monitoring chart.....93

Fig. 5.11. Visualization of the assembly line — operations for the manufacturing of a single object.94

Fig. 5.12. Visualization of the assembly line — multiple operations.95

Fig. 5.13. Visualization of the personpower in the assembly line for manufacturing the TI-500 Electronic watch.98

Fig. 6.1. Folding-up of a quantified bar chart, intensity personpower.103

Fig. 6.2. The hierarchical structure of the Visual Scheduling and Management System, application construction.....105

Fig. 6.3. The combined microtemplate for the formwork and reinforcing bars, intensity personpower.....106

Fig. 6.4. The hierarchical structure of the Visual Scheduling and Management System for a project without repeating tasks.109

Fig. 6.5. The matrix-balanced schedule for the structural skeleton composed of folded-up tasks, intensity personpower.115

Fig. 6.6. The matrix-balanced schedule for the structural skeleton indicating the discrete tasks that make the folded-up tasks, intensity personpower.116

Fig. 6.7. Time expansion and contraction of the matrix-balanced schedule for the structural skeleton, intensity personpower.117

Fig. 6.8. The scheduling, monitoring and updating process.....121

Fig. 7.1. The time scaled milestone chart.....128

Fig. 7.2. The Gantt chart or bar chart.129

Fig. 7.3.	A combination Gantt chart with milestones.....	129
Fig. 7.4.	The node and arrow notation.....	130
Fig. 7.5.	Nodes and arrows notation, tasks on the nodes network (precedence diagram).....	132
Fig. 7.6.	Nodes and arrows notation, tasks on the arrows network.....	133
Fig. 7.7.	Nodes and arrows notation, tasks on the arrows network with time dimension (time scaled network).....	134
Fig. 7.8.	Network with text information.....	136
Fig. 7.9.	The line of balance chart.....	137
Fig. 7.10.	Different repeating tasks represented on a line of balance chart.	138
Fig. 7.11.	Alternative scheduling for repeating tasks with the line of balance.....	139
Fig. 8.1.	Juxtaposition of a quantified bar chart to a Gantt chart and a network diagram.....	143
Fig. 8.2.	Juxtaposition of a bar in a Gantt chart to quantified bars displaying the assumptions on the resources.	145
Fig. 8.3.	Resource loading view for all the workers of the tasks shown in Fig. 8.1.	147
Fig. 8.4.	Juxtaposition of a quantified bar chart to a Gantt chart for the control of the project.....	153
Fig. 8.5.	Juxtaposition of a quantified bar chart to a Gantt chart for updating the project.....	155
Fig. 9.1.	Schematic elevation of the hotel, showing the use of floors and the identical floors from the 4th to the 22nd.....	162
Fig. 9.2.	Plan of the identical 18 floors (4th to 22nd floor), showing the shear walls, the beams and the core of the building.....	163
Fig. 9.3.	Preliminary connoting bar chart for the construction of a typical floor.....	165
Fig. 9.4.	The assignment of workers for marking the layout of the floor	167
Fig. 9.5.	The assignment of workers — Day 1 (8 am - 4 pm).....	168
Fig. 9.6.	The assignment of workers — Day 2 (8 am - 4 pm).....	170
Fig. 9.7.	The assignment of workers — Day 3 (8 am - 12 noon).....	171
Fig. 9.8.	The assignment of workers — Day 3 (12 noon - 4 pm).....	172
Fig. 9.9.	The assignment of workers — Day 4 (8 am - 4 pm).....	173
Fig. 9.10.	Microtemplate for reinforced concrete elements.	176

xii List of Figures

Fig. 9.11.	The template for the construction of the structural elements of a typical floor .	177
Fig. 9.12.	Matrix-balanced chart for the construction of the structural frame, including the moving of the formwork and the scaffolding from floor to floor.	179
Fig. 9.13.	Plan and elevation of a typical bathroom.	180
Fig. 9.14.	Micro template for the twelve bathrooms of a floor.	182
Fig. 9.15.	Matrix-balanced chart for the twelve bathrooms of a floor.	184
Fig. 9.16.	Micro template for the twelve guest rooms of a floor.	185
Fig. 9.17.	Combined matrix-balanced chart for bathrooms and guest rooms.	186
Fig. 9.17.	Combined matrix-balanced chart for bathrooms and guest rooms.	187
Fig. 9.18.	Finishing schedule by trade.	188
Fig. 9.19.	Correction of schedule for compensating delays.	189
Fig. 10.1.	The initial scheduling for the renovation of the nine floors.	195
Fig. 10.2.	The initial Gantt chart for planning the renovation of the 26th floor.	196
Fig. 10.3.	The architectural drawing of the renovation of the 26th floor.	197
Fig. 10.4.	The initial template for scheduling the renovation of the 26th floor.	200
Fig. 10.4.	The initial template for scheduling the renovation of the 26th floor (continued).	201
Fig. 10.5.	A study to level the personpower on the 26th floor, keeping the same deadline	205
Fig. 10.5.	A study to level the personpower on the 26th floor, keeping the same deadline (continued).	206
Fig. 10.6.	A study to level the personpower on the 26th floor, extending the deadline by one week.	206
Fig. 10.6.	A study to level the personpower on the 26th floor, extending the deadline by one week (continued).	207
Fig. 10.7.	The control template of October 23 (in progress), for the renovation of the 26th floor.	210
Fig. 10.7.	The control template of October 23 (in progress), for the renovation of the 26th floor (continued).	211
Fig. 10.8.	The control template at the completion of the renovation of the 26th floor.	214

Fig. 10.8.	The control template at the completion of the renovation of the 26th floor (continued).	215
Fig. 10.9.	The architectural drawing of the renovation of the 34th floor.	219
Fig. 10.10.	The combined template for scheduling the renovation of the 34th floor, MIS & Library (continue).	220
Fig. 10.10.	The combined template for scheduling the renovation of the 34th floor, MIS & Library.....	221
Fig. 10.11.	The matrix-balanced chart for planning the renovation of the 34th floor, MIS & Library (week-end displayed).	223
Fig. 10.12.	An alternative matrix-balanced chart for planning the renovation of the 34th floor, MIS & Library (week-end not displayed).....	224

List of Tables

Table 3.1.	Characteristics of selected aircrafts, for maximum range and for maximum payload.	55
Table 4.1.	Data to generate the template shown in Fig. 4.1.	62
Table 5.1.	Assembly flow, time estimates and personnel requirements for final assembly of the TI-500 electronic watch.	97
Table 6.1.	Data for the various floors of the building, task concrete.	111
Table 6.2.	Data for the various floors of the building, tasks formwork and reinforcing bars.	113
Table 6.3.	Data for the various floors of the building, task M&E installations and calculation of total duration for all floors.	114
Table 7.1.	The milestone chart.	127
Table 9.1.	Quantities of materials	166
Table 9.2.	Assignment of workers per structural element, on a daily basis.	174
Table 9.3.	Changes in duration, in days, as compared to the original schedule.	190
Table 10.1.	Productivity by task, estimated and actual.	217

Acknowledgments

The work presented in this book is the product of my research on *Task Management* at Harvard University. During the 1987-88 academic year, Mr. Yasuo Ueda, co-inventor of the patent, project manager of Shimizu Corporation of Japan and graduate student at Harvard University, worked extensively on this system. The following years, Mr. Masaji Kominato and Mr. Hiroshi Mimura worked to advance the system further. Mr. Mimura, in collaboration with Mr. David Shrestinian of Beacon Construction, prepared the data for the last two chapters of this book. Since the origination of this project in 1987, Prof. Daniel L. Schodek, of Harvard University, has been instrumental in the development of the system.

In 1991-92, during my Visiting Professorship at Bouwkunde, Technische Universiteit Delft, I had many interesting and challenging discussions with Prof. S. Menheere and Prof. A. Tzonis, and I prepared the first book on this system, entitled *A Visual Representation System for the Scheduling and Management of Projects*, published by TU-Delft.

Furthermore, over a number of years, I had fruitful discussions on the concepts contained in this book with many colleagues, among them Dr. D. Angelides, Prof. J. Bakos, Mr. F. Basius, Prof. D. Halpin, Dr. H. Irwig, Mr. J. Macomber, and Mr. J. Yagi.

Spiro N. Pollalis
Cambridge, Massachusetts
May 1993